Contour 21+ 75cm Projection Wall Mounted Rimless WC Suite

ILLUSTRATED				
S0442	Contour 21+ 75cm projection wall mounted rimless WC pan with horizontal outlet and anti-microbial glaze			
S1347	Conceala 3 single flush 6 litre cistern, side inlet, lever operated, easy adjustable to low water volumes, internal overflow, flushpipe and lever included			
S4066	Contour 21 toilet seat only, top fixing hinges and retaining buffers			
S9139	Support bracket for wall mounted WC raised height with bolts			
S6466	Contour 21 back support rail for 75cm projection WC, 40 x 22 x 35mm diameter tube			
S6884	Cushion for back support with clips, new design			


OPTIONS

S3326	Conceala 3 dual flush 6/4 litre cistern, side inlet, pneumatic actuation, easy adjustable to low water volumes (4.5/3 or 4/2.6 litres), internal overflow, flushpipe included, no button/flushplate
S3330	Conceala 3 single flush 6 litre cistern, bottom/top inlet, lever operated, easy adjustable to low water volumes (4.5 or 4 litres), internal overflow, flushpipe included, no lever
E4463	Karisma pneumatic flush plate, dual flush, unbranded for Conceala 3 cisterns
S4516	Lever flushing spatula for Conceala cistern
S4300	Panekta outlet connector to convert horizontal outlet wcs to S or turned P trap
S4305	Panekta outlet connector to convert horizontal outlet wcs to P trap

ILLUSTRATED PRODUCT DETAILS

Weights		Finishes	
S0442	37.00 KG	S0442 White With	
S1347	2.70 KG	SmartGuard (HY)
S4066	1.55 KG	S1347 Chrome (AA)	
S9139	4.28 KG		
S6466	0.62 KG	S4066 White (01)	
S6884	4.00 KG	34000 Willie (01)	
Materia	ls	S9139 Neutral/No Finis	sh
S0442	Vitreous China	(67)	
S1347	Plastic	\$6466 White (AC)	
S4066	Plastic	Willie (AC)	
S9139	Metal		
S6466	Aluminium	S6884 Neutral/No Finis	sh
S6884	Mixed Material	[] (67)	
		Designer	
		Robin Levien, RDI	
FINISH	H OPTIONS		





FEATURES














Contour 21+ 75cm Projection Wall Mounted Rimless WC Suite



Standards

Vitreous china to BS3402. WC pan to BS EN 997 and BS EN 33

Special Notes

S9139 support brackets secured to floor within the duct, WC fixed to support brackets with new hidden fixation set supplied. Joint sealed with waterproof sealant (not supplied). "Currently not recommended for In wall support systems"

